

Town of Ridgeland, SC

Request for Proposals (RFP)

Sewer System Flow Monitoring and Smoke Testing

Addendum #1 November 15, 2016

Item #1 – Additional method for Pump Station Flow Metering:

Attachment “A” Scope of Services currently states *“Install real-time continuous recording digital downloadable flow meters on the force main for each of the 15 sewer pump stations are listed below...”*

Amend Attachment “A” Scope of Services under Pump Stations to read as follows:

“Install real-time continuous recording digital downloadable flow meters on each of the 15 sewer pump station by means of:

- *Installation of a force main mounted continuous flow meter and/or;*
- *Installation of an in-line gravity system flow meter in the receiving manhole or each pump station. If this method is proposed by the Vendor, the Vendor will be responsible for ensuring that the existing gravity sewer between the receiving manhole and wetwell is clear of debris and sediment so as not to impact the accuracy of the in-line flow meter.”*

Item #2 – Clarification on data review:

For the purpose of this RFP, the Vendor should assume that they will provide data to the Town on Excel compatible spreadsheets. At this time, the Town intends to have a third party engineering consultant review the correlated data from each location where a monitoring station is set.